



भारत सरकार
खान मंत्रालय
भारतीय खान व्यूगें
क्षेत्रीय खान निगंत्रक का कार्यालय
माखूपुरा औद्योगिक क्षेत्र, अजमेर 305002



सीड पोस्ट
GOVERNMENT OF INDIA
MINISTRY OF MINES
INDIAN BUREAU OF MINES OFFICE OF
REGIONAL CONTROLLER OF MINES
Makhupura Ind. Area, Ajmer - 305002

संख्या: राज/खान/चुनापत्थर-01/2022

खानकोड 38RAJ/1001

दिनांक: 19-09-2022

सेवामें,

श्री संदीप कुमार सिंह, खान एजेंट,
मेमर्स अंबुजा सीमेंट लिमिटेड,
राम चुनापत्थर खान, पोस्ट राबरियावास, तहमील-जैतारण
पाली-306709

विषय: राजस्थान राज्य के पाली जिले के जैतारण तहमील के राम गांव में स्थित आपकी राम-2 चुनापत्थर खान में खनिज संरक्षण एवं विकास नियमावली, 2017 के नियमों का उल्लंघन

महोदय,


अद्योहस्ताक्षरी द्वारा दिनांक 03.08.2022 को आपकी उपस्थिती में उपरोक्त खान का निरीक्षण किया गया था और खनिज संरक्षण एवं विकास नियमावली, 2017 के निम्नलिखित नियमों का उल्लंघन पाया गया है।

नियम	उल्लंघन के प्रकार का विस्तृत व्योरा
11(1)	<p>The mining operations in the lease area are not carried out as per modified mining plan approved vide letter No. 584(4)(3)(1877)/2021 RCOM Ajmer dated 16.08.2021 and following deviations are observed during inspection.</p> <p>(a) It was planned & proposed to work in Northern Western Ridge, Sub Western Ridge, Western Ridge, Eastern Ridge and temple hill to achieve 35,99,700t ROM limestone production. It is observed during inspection and from submitted drone image that development & production in between grid lines N3300-3400 on temple hill, N2500-2900 in eastern ridge not carried out and total ROM production during the year was 25,37,074t only. The achieved production was 30% lesser than the target due to purchase of 3,46,910t minor mineral limestone from the various traders/dealers and the limestone is sourced from the nearby minor mineral lease holders. The achieved production during last 5-6 years was less than 40% of the target in these years.</p> <p>(b) It was planned & proposed to dump the IB waste by advancing W2 between gridline N3800-N4200 and by advancing W3 from gridline N5780-N5880 during the years 2021-22. It is observed during inspection, updated plan & sections and drone image that dump W2 and W3 are not advanced at the proposed location. The IB waste material has been dumped over existing dumps indeviation of the proposals.</p>
32(1)(b)	<p>a) The updated geological plan as on 31st March 2022 is not showing the exploration carried out during the year 2021-22; although proposed 13 boreholes during the year are reported as completed.</p>
32(5)(b)	<p>a) The updated environment plan as on 31st March 2022 is not showing the constructed retaining wall and garland drain during the year 2021-22; although proposed 440m and 425m garland drain during the year are reported as completed by constructing 450m retaining wall & 425m garland drain. The work done under progressive mine closure plan during the year is reported zero for the year 2021-22 in item-12 of Part-I in the annual return.</p>

45(5)(b)	<p>Following deficiencies are observed in the annual returns of the mines submitted for the year 2021-22 in Form-G-1.</p> <p>(a) The cost of electricity generated, tyres, drill rods is reported zero in Part-III.</p> <p>(b) Total quantity of Overburden/Waste removed during the year is reported zero in Part-V Item 4.2(C), although interburden waste removed & dumped.</p> <p>(c) The pulverization details in table 3 of Part-VI is not filled; although crushing activity is carried out within lease area and screen reject is also reported.</p> <p>(d) The cost of pulverization is reported ₹ 0.00 per tonne in Part-VI item 3(ii) and not separately shown in the cost of production.</p>
----------	--

03. उपरोक्त नियम का उल्लंघन खनिज संरक्षण एवं विकास नियमावली, 2017 के नियम 62 के अन्तर्गत दंडनीय अपराध है और खनिज संरक्षण एवं विकास नियमावली, 2017 के नियम 45(7)(a) के अन्तर्गत खान में खनन प्रचालनों और प्रेषणों को निलंबित का आदेश भी जारी किया जा सकता है।

04. अतः आपको सलाह दी जाती है कि आप उपरोक्त उल्लंघन का अतिशीघ्र सुधार करें एवं इसके सुधार की स्थिति की जानकारी इस पत्र के जारी होने की दिनांक से 45 (पैंतालीस) दिनों के भीतर इस कार्यालय को सूचित करें।

भवदीय

19.09.2022
(गिरीश कुमार जांगिड)
क्षेत्रीय खान नियंत्रक