

**Government of India**  
**Ministry of Mines**  
**Indian Bureau of Mines**  
**Office of the Regional Controller of Mines, Jabalpur**

To,

Shri. Kailesh Chandra Jhanwar, Nominated Owner and Director  
M/s Ultra Tech Cements Ltd.,  
901, Satguru Towers, JN of North and Central  
Santa Cruz West, Mumbai,  
Maharashtra – 400054  
Email : kailashjhanwar@adityabirla.com,

Sub: Violation of provisions of Mineral Conservation and Development Rules, 2017, (MCDR, 2017) in respect of Tiloura Limestone Mine (193.252 hectare) Mine Code 38MPR35113 in District Satna of Madhya Pradesh State regarding.

Sir,

Following provision of Mineral conservation and Development Rules 2017 were found violated in respect of your subject mine during the inspection of the said mine by the undersigned on 24.10.2024 in the presence of Shri P K Upadhyaa, Agent, Dr Vivek Bharadwaj, Geologist, Shri Swarnim Salecha, Mines manager.

Rule No	Nature of violation observed in detail
<b>Rule 11(1)</b>	<p><i>No holder of a mining lease shall commence or carry out mining operations in any area except in accordance with the mining plan approved, modified or reviewed by the Indian Bureau of Mines or prepared and certified in accordance with the system established by the State Government pursuant to the proviso to clause (b) of sub-section (2) of section 5.</i></p> <p><i>Mining operations are not found carried out in accordance with approved Modification of approved Mining plan vide letter no. No. E 2743 MCDR-MPC0LST/18/2022-JBP-IBM_RO_JBP dated 30.03.2023 as below:</i></p> <ol style="list-style-type: none"> <li>1. It was approved to carry out exploration by drilling 06 no. of bore hole with 240 meterage during the year 2024-25; against which no exploration was started so far.</li> <li>2. Dumping is being carried out in 7.5 meters safety zone over height of 3 to 4 meters in between BP's 39 to 46 without having any such approved proposals.</li> <li>3. It was approved to generate 120049 cum of waste during the year 2023-24; against which 5980 cum is generated, thus development is on lower side.</li> <li>4. It was approved to construct Retaining wall along bottom periphery of waste dump viz. 240 meters during the year 2023-24 and 160 meters during 2024-25: No retaining wall constructed during the year 2023-24 and no work started for the</li> </ol>

	year 2024-25 till date of inspection, resulting wash off of dumps is observed.
<b>34A</b>	<i>Drone data submitted for the year 2023-24 is not as per SOP in DDMS portal.</i>
<b>45(7)</b>	<p>Following discrepancies are observed in the Annual return for the year 2023-24</p> <p>(i) PART-I, item no.11(iv), Period of lease shall be furnished correctly from the date of execution, its 55 years</p> <p>(ii) PART-VI item no. 3(ii)</p> <p>Ore is being transported to cement plant for about 13-14 KMs from lease area and the transportation cost for the same shall be deducted from the Ex mine price, as ex mine price shall be computed up to Pit Head only, thus item no. 04 the transportation cost from pit head to cement shall be furnished and cannot be Nil, accordingly PART-VI, item -3(ii) &amp; item 4 shall be modified.</p>

02. In this connection, it is brought to your notice that the above violations constitute an offence punishable under Rule 62 of MCDR, 2017.
03. Non-compliance of the rule 11(1) & 45(7) of MCDR,2017 may lead to suspension of Mining operations under the provisions of rule 11(2) & 45(7)(a) of MCDR,2017.
04. You are advised to rectify the above violations immediately and intimate the position to this office within 45 (Forty Five) days from the date of issue of this letter.

Yours faithfully

(Ibrahim Sharif)  
Dy. Controller of Mines,  
For Regional Controller of mines

Copy for kind information:

- 1) The Director, Directorate of Geology & Mining, Khanij Bhavan, 27/8, Raja Ram Mohan Rai Marg, Lucknow-226001 (U.P.); Mining Lease boundary pillars are not found erected as per MCR,2016
- 2) Collectorate, Maihar District, Madhya Pradesh
- 3) खान नियंत्रक (मध्य), भारतीय खान ब्यूरो, नागपुर

(इब्राहिम शरीफ )  
उप खान नियंत्रक,  
क्रुते क्षेत्रीय खन नियंत्रक